

All Furniture Installation

675 Stinson Blvd. #100 Minneapolis MN 55413 Ph: 612-238-3200 Fax: 612-238-3201

Guidelines for Panel Lift

1. Provide bookcarts and boxes for employees to unpack system, unloading system allows system to be lifted easier without stress on the system.
2. Movers to remove all freestanding furniture, label as necessary. This will allow carpet installers to spread adhesive more thoroughly, also ease of installation. (Less chance of carpet tile shifting.)
3. Remove carpet up to panel system.
4. Lift panel system, demo carpet and replace panel system. (By replacing system it minimizes stress on panels.)
5. Spread adhesive.
6. Carpet installers to install carpet, panels to be lifted and replaced as necessary.
7. Replace furniture and bookcarts.
8. Re-level all panel systems, straighten all panel runs, and check all electrical connections.
9. All carpet demo will be hauled away daily.